

Zpevnění skládek															
km 0,007 - 0,093 - vpravo				km 0,007 - 0,093 - vlevo				km 1,140 - 1,245 - vpravo				km 1,591 - 1,688 - vlevo			
staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha
(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )
0,007	0,0	x	x	0,007	0,0	x	x	1,140	0,0	x	x	1,591	0,0	x	x
0,017	6,0	10,0	30,00	0,017	3,0	10,0	15,00	1,147	24,0	7,0	84,00	1,610	6,0	19,0	57,00
0,027	9,0	10,0	75,00	0,027	4,0	10,0	35,00	1,198	30,0	51,0	1377,00	1,628	6,0	18,0	108,00
0,037	12,0	10,0	105,00	0,037	7,0	10,0	55,00	1,245	0,0	47,0	705,00	1,643	5,0	15,0	82,50
0,047	16,0	10,0	140,00	0,047	10,0	10,0	85,00					1,669	3,0	26,0	104,00
0,057	16,0	10,0	160,00	0,057	15,0	10,0	125,00					1,682	3,0	13,0	39,00
0,067	15,0	10,0	155,00	0,067	13,0	10,0	140,00					1,688	0,0	6,0	9,00
0,077	12,0	10,0	135,00	0,077	7,0	10,0	100,00	výřez - 200 m2 1 ks pařezu do 30 cm Úph + 100 ŠD 0/63				výřez - 10 m2 Úph + 100 ŠD 0/63			
0,087	6,0	10,0	90,00	0,087	4,0	10,0	55,00								
0,093	0,0	6,0	18,00	0,093	0,0	6,0	12,00								
ODK - km 0,000 - 0,027 = 125 m2 Úph + 100 ŠD 0/63				Úph + 100 ŠD 0/63											
Plocha celkem (m <sup>2</sup> ):			908,00	Plocha celkem (m <sup>2</sup> ):			622,00	Plocha celkem (m <sup>2</sup> ):			2166,00	Plocha celkem (m <sup>2</sup> ):			399,50
km 2,600 - 2,721 - vpravo				km 2,596 - 2,650 - vlevo				km 2,758 - 2,804 - vpravo				km 2,840 - 2,889 - vpravo			
staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha
(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )
2,600	0,0	x	x	2,596	24,0	x	x	2,758	0,0	x	x	2,840	0,0	x	x
2,605	12,0	5,0	30,00	2,650	9,0	54,0	891,00	2,763	4,0	5,0	10,00	2,852	5,0	12,0	30,00
2,650	20,0	45,0	720,00	výřez 1/3 plochy = 297,00 Odk + Úph + 100 HDK 32/63 + 100 ŠD 0/63				2,785	7,0	22,0	121,00	2,874	5,0	22,0	110,00
2,672	14,0	22,0	374,00					2,800	7,0	15,0	105,00	2,889	0,0	15,0	37,50
2,721	0,0	49,0	343,00					2,804	0,0	4,0	14,00	ODK 100 + Úph + 100 HDK 32/63 + 100 ŠD 0/63			
výřez - 40 m2 ODK + Úph + 100 HDK 32/63 + 100 ŠD 0/63															
Plocha celkem (m <sup>2</sup> ):			1467,00	Plocha celkem (m <sup>2</sup> ):			1188,00	Plocha celkem (m <sup>2</sup> ):			250,00	Plocha celkem (m <sup>2</sup> ):			177,50

stavba: Rekonstrukce lesní cesty "Lví"

**Tab. 3**

Zpevnění skládek															
km 3,174 - 3,273 - vlevo				km 4,128 - 4,205 - vpravo											
staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha	staničení	šíře	vzdál.	plocha
(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )	(m)	(m)	(m)	(m <sup>2</sup> )
3,174	0,0	x	x	4,128	0,0	x	x			x	x			x	x
3,191	11,0	17,0	93,50	4,137	2,0	9,0	9,00			0,0	0,00			0,0	0,00
3,215	11,0	24,0	264,00	4,148	5,5	11,0	41,25			0,0	0,00			0,0	0,00
3,248	7,0	33,0	297,00	4,156	7,5	8,0	52,00			0,0	0,00			0,0	0,00
3,273	0,0	25,0	87,50	4,181	13,0	25,0	256,25			0,0	0,00			0,0	0,00
ODK 100 + Úph HDK 32/63 - 200 mm ŠD 0/63 100 mm				4,205	0,0	24,0	156,00			0,0	0,00			0,0	0,00
				Úph ŠD 0/63 100 mm						0,0	0,00			0,0	0,00
										0,0	0,00			0,0	0,00
										0,0	0,00			0,0	0,00
										0,0	0,00			0,0	0,00
Plocha celkem (m <sup>2</sup> ):			742,00	Plocha celkem (m <sup>2</sup> ):			514,50	Plocha celkem (m <sup>2</sup> ):			0,00	Plocha celkem (m <sup>2</sup> ):			0,00

Celkem:	ODK (odhumusování)	100	3949,50	(m <sup>2</sup> )
	Úph	–	8434,50	(m <sup>2</sup> )
	HDK 32/63	100	3082,50	(m <sup>2</sup> )
	HDK 32/63	200	742,00	(m <sup>2</sup> )
	ŠD 0/63	100	8434,50	(m <sup>2</sup> )